



अधीक्षण अभियंता का कार्यालय
OFFICE OF THE SUPERINTENDING ENGINEER
कार्य स्थापना अनुभाग, **WORKS ESTABLISHMENT SECTION**
राष्ट्रीय प्रौद्योगिकी संस्थान कर्नाटक, सुरतकल
NATIONAL INSTITUTE OF TECHNOLOGY KARNATAKA,
SURATHKAL

पोस्ट श्रीनिवासनगर, मंगलूरु – 575025, कर्नाटक, भारत. / Post Srinivasnagar, Mangaluru – 575025, Karnataka, INDIA.
Phone: [0824] - 2473029, 2473028 Email: se@nitk.edu.in Website: <http://www.nitk.ac.in>

No: SE/Elec/2026-27/Tech(E)/MESCOM/1/

Date: 22.04.2026

NOTICE INVITING QUOTATIONS

The National Institute of Technology Karnataka, Surathkal (in short - NITK, Surathkal or Institute) is an autonomous Institute of the Govt. of India [under the Ministry of Education - MoE] imparting technical and science education. The Institute intends to invite quotations for the work of “**Replacement of current transformers at 33KV sub station and load enhancement work in NITK**”. The details of work is listed in the sheet enclosed. In this connection, sealed quotations are invited by the undersigned subject to the terms and conditions enumerated here under from the contractors / manufacturers/ authorized dealers/ agencies so as to reach this office on or before **29 -04-2026 at 09:30 AM**. The quotations shall be opened possibly on the same day.

Terms and Cconditions:

1. The intending bidder shall quote his rates in the ‘**Quotation Format**’ enclosed here with either in his letter head or using the same format. He shall sign each page with seal of the firm. Envelop super scripted as Quotation for “**Replacement of current transformers at 33KV sub station and load enhancement work in NITK**” due on **29-04-2026 at 09:30AM** and addressed to as “The Superintending Engineer, NITK, Surathkal, Post Srinivasnagar, Mangaluru – 575025” be sent so as to reach this office on or before the due date mentioned.
2. The GST registration number, CPWD / MESCOM license copy, certificate and the PAN number of the bidder shall be enclosed along with the quotation. Quotation without this information will not be accepted.
3. Quotation may be dropped in the Tender Box kept in the office or may be sent by post/ courier. It is the responsibility of the bidder to make sure that the quotation is delivered in time. The quotations received after the due date will not be entertained.
4. The payment shall be made part bill basis and billing will be done on the basis as per the recommendation of the Engineer – in – charge. No interest will be paid for delayed payments if any.
5. The rate quoted should be firm. No claim for enhancement of rate is admissible after opening of the Quotations.
6. It is the responsibility of the bidder to visit the site and analyse the nature of work before quoting the rate.
7. Terms and conditions stipulated in this Notice inviting conditions are binding on the bidder.
8. The undersigned reserve the right of rejecting all the quotations without assigning any reasons thereof.
9. Quotation validity should be minimum 6 months (60 days).

Sd/-
Superintending Engineer
NITK, Surathkal

Name and Address of the Bidder:

Name and Contact No:

MESCOM / PWD Licence no:

GST registration number:

PAN number:

No:

Date:

QUOTATION

To

The Superintending Engineer,
Office of the Superintending Engineer,
N.I.T.K, Surathkal.

Sl. No	Scope of work & Description of the items	Quantity	Rate in Rs. per each (without Tax)	Amount in Rs.
1.	<p>a) Supplying, erection, wiring, commission and testing of outdoor type current transformer with following specification (as per MESCOM approval): Rating: 40 – 75A / 1-1-1A(As per MESCOM approval) Voltage range; 33KV Type: outdoor, oil cooled live tank CT Class : 0.1, 0.2s, 0.2, 0.5s, 0.5, 1, 3, 5 (as per MESCOM approval) Burden: Up to 30VA (As Per MESCOM approval) Frequency: 50Hz No. Of CT's : – 3 nos The CT must adhere strictly to MESCOM (Mangalore Electricity Supply Company Limited) standards. Make : Kalpa / MESCOM approved.</p> <p>b) The work includes supply, erection, installation, commissioning, testing and energizing work complete as per MESCOM standards.</p> <p>c)The work includes carefully dismantling of existing CT's and other accessories and hand overing it to the dept / MESCOM.</p> <p>d)The work includes labour, tools & plants, transportation charges, crane charges, loading & unloading charges etc complete.</p> <p>e) The work includes preparation of general arrangements, arranging site inspections, preparation of drawings, modification of existing mounting</p>	One job work		

	<p>structures or civil foundations to accommodate the new CT dimensions. etc as per MESCOM norms.</p> <p>f) Coordination of the mandatory factory visit for inspection of CT's including all logistics.</p> <p>g) Updating existing control panels wiring, re-wiring protection circuits, and updating relay/meter settings to match the new CT ratios and burdens, Programming of numerical relays and energy meters etc.</p> <p>h) Submission of final test reports and obtaining the Work Completion Certificate from MESCOM.</p>			
	GST			
	Total amount			

(In words:

Seal & Signature of the Bidder